

Port of Townsville Channel Upgrade Project

Geotextile design considerations for 'closed' rock bund reclamation structures





United Nations Sustainable Development Goal – to build **resilient infrastructure**, promote inclusive and sustainable industrialisation and **foster innovation**

Geotextiles design considerations for ‘closed’ rock bund reclamation structures

1. Project Background
2. Geotextile design considerations / lessons learnt
3. R&D

Project Background

Capital Dredging with the Great Barrier Reef Marine Park



Project Timeline

2018
Environmental
approvals
received

April 2019
Up to 800,00 tonnes of
rock commenced
delivery for 2.2km of
rock wall



March 2020
Start of rock wall
construction

Project Timeline

June 2021

Interim rock bund
complete



March 2022

Dredging
commences

July 2021

Construction of
TUF




Interim bund



Project Timeline



March 2024
Dredging complete



October 2024
Permanent rock wall complete




Interim Rock Bund


62ha Of reclamation

Over **800,000** tonnes of rock



Geotextile lined bund





Temporary Unloading Facility






Rock Bund Build




Bund Structure Build






Geotextile lining






Clay lining



Clay lining



Rear Crest Scour Protection



Geotextiles design considerations for 'closed' rock bund reclamation structures

1. Project Background
2. Geotextile design considerations / lessons learnt
3. R&D




Geotextile Design Considerations

Dry Trials - Testing for Strength/ Elongation




geotextiles

Survivability Chart




Geotextile Design Considerations

Dry Trials - Testing for Strength/ Elongation



Geotextiles design considerations

1209RP non-woven needle punched geotextile



AnAqSim™

Rock – 1000 m/day



1209RP – 145 m/day

Clay lining – 0.001 m/day



Geotextile design considerations

Transmissivity/ permeability and hydraulic stability





Geotextile design considerations

Tidal lag estimates

AnAqSim™

Scenario	Linear Extent of Clay Lining (Chainage, m)	+4.1m	+3.6m	+3.0m
		LAT Tide	LAT Tide	LAT Tide
		Predicted Tidal Lag (m)		
1	0	1.5	1.2	0.8
2	550	1.5	1.2	0.8
3	1075	1.8	1.4	0.9
4	1625	2.0	1.5	0.95
5	2177* (fully clay lined)	2.1	1.6	1.0

*values estimated, not modelled



Scenario 1 Fully geotextile lined (no clay)

Scenarios 2 to 5 Progressive clay lining


Geotextile design considerations

Model validation

AnAqSim™

Scenario	Linear Extent of Clay Lining (Chainage, m)	+4.1m	+3.6m	+3.0m
		LAT Tide	LAT Tide	LAT Tide
		Predicted Tidal Lag (m)		
1	0	1.5	1.2	0.8
2	550	1.5	1.2	0.8
3	1075	1.8	1.4	0.9
4	1625	2.0	1.5	0.95
5	2177* (fully clay lined)	2.1	1.6	1.0

*values estimated, not modelled



Scenario 1 Fully geotextile lined (no clay)

Scenario 2 to 4 Progressive clay lining




Geotextile design considerations


Flow Theory

Steady Flow in an Unconfined Aquifer

- $K = 10^{-1}$ cm/sec
- $L = 150$ m
- $h_A = 6.5$ m
- $h_B = 4$ m
- $x = 150$ m
- Find Q



$$Q = \frac{K}{2} \frac{h_B^2 - h_A^2}{L} = \frac{86.4 \text{ m/d}}{2} \frac{6.5^2 - 4^2}{150} = 7.56 \text{ m}^3 \text{ d/m}$$



Geotextile design considerations

TEXCEL 1209RP NONWOVEN STAPLE FIBREGEOTEXTILES


The values published in this leaflet are to the best of our knowledge true and correct. The product specification may change at any time without prior notice. **No warranty is expressed or implied.** Manufactured by Geofabrics Australasia Pty Ltd to the ISO 9001 Quality Management System Standard.

PROPERTY	TEST METHOD	UNITS	VALUE ¹
Fibre Type	Polyester/Polypropylene		
Mass	AS3706.1	g/m ²	2,200
Thickness	AS3706.1	mm	12
Bond Strength of Geocomposite Ply Adhesion	ASTM D7005	N/m	6000
CBR Burst Strength	AS3706.4	N	13,200
Wide Strip Tensile Strength MD	AS3706.2	kN/m	50
Wide Strip Tensile Strength XMD	AS3706.2	kN/m	85
Wide Strip Tensile Elongation MD	AS3706.2	%	100
Wide Strip Tensile Elongation XMD	AS3706.2	%	85
Abrasion Resistance MD/XMD	BAW Rotating Drum	% Strength Retained	>75
Hydrocarbon (Diesel) Resistance MD/XMD	AS3706.12	% Strength Retained	>90
UV Resistance 500 Hours	AS3706.11	% Strength Retained	>90
Pore Size O95 - Sieve Method	AS3706.7	µm	<75
Permittivity	AS3706.9	s ⁻¹	0.15
Coefficient of Permeability	AS3706.9	m/s x 10 ⁻⁶	16.8
Flow Rate @ 100mm head	AS3706.9	l/m ² /s	15

1. All values are typical, 2. MD=Machine Direction, 3. XMD= Cross Machine Direction

Scenario	Linear Extent of Clay Lining (Chainage, m)	+4.1m LAT Tide	+3.6m LAT Tide	+3.0m LAT Tide
1	0	1.5	1.2	0.8
2	550	1.5	1.2	0.8
3	1075	1.8	1.4	0.9
4	1625	2.0	1.5	0.95
Fully clay lined*	2177	2.1	1.6	1.0



*values estimated, not modelled



Geotextiles design considerations for 'closed' rock bund reclamation structures

1. Project Background
2. Geotextile design considerations / lessons learnt
3. R&D





Key conclusions



Limited design guidance available



Geotextile survivability



Permeability of geotextile should be assessed by a suitably qualified hydrogeologist



Modelling construction staging for geotextile lining and clay backing



**Geotextile R&D – Watch this space!
PIANC Working Group?**

Any Questions?





For 75 years, SMEC has built a reputation as a trusted partner on major Transport, Water and Energy projects around the world.

SMEC is committed to positively impact the people, the environment and the clients and communities we serve. Through our network of global specialists, our specialist teams draw on deep expertise and systems thinking to simplify the complex and deliver integrated engineering solutions across a range of diverse environments.