

Introduction





Project Location







Site Layout







Scope of Works

Dredging

- 1. Dredging Teggs Channel
- 2. Dredging Boat Harbour Channel
- 3. Dredging *new* Fascine Entrance Channel

Dune Construction

- Reclamation all material to Baggable Island Spit to deisgn profile
- Sand stabilisation & revegetation





Project Challenges & Achievements

- Accelerated timeline due to Government commitments
- Dune design flexible to accommodate unknown volume
- Clays in Fascine dredge area → impacts on dredging and reclamation
- Mix of dredging conditions and minimal downtime
- High indigenous engagement (employment and spend)



Dredging Works



Dredge Selection: competing interests

Cutter Suction Dredge

- Offshore maintenance dredging exposed to wind and sea
- Capital new-channel dredging protected by spit

Selected 3-point anchored CSD with high pumping capacity






Auxiliary Equipment


- Anchor Handling Vessel (AHV)
- Crew / Tender / Safety Vessel
- ~2km DN400 pipeline
- Booster Pump
- Swamp-track Dozers (D6)
- Excavator (30T)
- IT Loader (966)





Maintenance Dredging








Capital Dredging – new channel









Dredging Works – summary

- Teggs Channel: 36,000m³ from July to September 2023
- Fascine new channel: 101,000m³
 from October to December 2023
- Boat Harbour Approach 16,000m³
 in January 2024



Reclamation Works & Dune Construction



Reclamation of dredge spoil

- Initial swale system – high retention time = maximum material capture
- Working area decreased as dune was completed














Dune Construction

- Final dune shape was to mimic a natural dune.
- Design allowed wide tolerances but required surface variety in 3 directions
- To minimise re-working to the specification, material was captured at the outfall point and immediately shaped to the final design while 'wet'
- The final dune shape to its final design "grew" as the dredging progressed






Dune Construction – Design & Setout





Dune Construction – Progress Survey





Dune Construction – Fascine & Clays





Stabilisation – Drift Fence and Matting





(Ex) Tropical Cyclone Lincoln







Result: Completed Dune Construction











Additional (& unexpected) Work Scopes

- NavAid removal added to scope to allow dredging works
- Old Jetty Piles found within dredge footprint (Heritage jetty of significance)
- Marine Fauna monitoring
- Turtle nests & hatchlings identification and management





Historic Jetty Piles

- Dive Team mobilised for rigging and removal
- Extracted using AHV onsite
- Inspected and catalogued by WA Museum archaeologist
- Buried locally on the spit






Turtle Nests & Hatchlings









UN SDG #10: Reduced Inequalities





Strategic long-term partnerships produce best results



29.5% Indigenous employment by person-hours on site



UN SDG #14: Life Below Water



PROTECT AND RESTORE ECOSYSTEMS



CONSERVE COASTAL AND MARINE AREAS

- Contractors "on the front line" on marine projects
- Whole site crew should be conscious of environmental impacts
- Taking an active role in monitoring, reporting and compliance is key



Acknowledgements











Questions?



